



Underfloor Heating installation at Severn Quay, Chepstow

Designed and Installed by Certus Construction 2023



Certus Construction have been appointed by Concept Mechanical to design and install the Underfloor Heating for the latest release of 25 Town Houses built in 5 Blocks at Wynndel Property Severn Quay development in Chepstow. Underfloor Heating has been provided to the Ground Floors only of the 25 properties.

Certus designed the Underfloor Heating system with our manufacturing partner Reliable, including ZL 117503 Stainless Steel manifolds and 16mm PE-RT Underfloor pipe. Heatmiser Programmable Neo Thermostats provide individual room control, and with the option of a Neo Hub providing in-home and remote access, homeowners can adjust individual rooms from tablet or mobile devices.

Certus also installed the Ground Floor insulation and screed and so provided the complete “Heated Floor Solution” for this prestigious site development.

Certus Project Value	£50,000
Main Build Contractor	BECT Building Contractors
Mechanical Contractor	Concept Mechanical
Client	Wynndel Property Company



www.certus.construction

tel 01291 630120

Email info@certusconstruction.co.uk